The 30th January 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 28th February 1888, for restoring Holalu Tank, Registered No. 866, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Items of Work.	Per.	Quantity.	Rate.
Bund—			
Earthwork	C. Yd.	9,713	
Rough stone work, new	Do	4,435	
Do old	Do	712	
Grade stones	No.	41	
B. M. stones	Do	2	
Turfing	Sqr.	2,640	
Sluice—			
Repairs to both sluices	Lump sum.	..	
Waste Weirs—			
Extension of Kodi by cutting high ground soft rock ..	C. Yd.	3,200	
Burnt brick in surki mortar	C. Ft.	1,087	
Surki plaster	Sqr.	639	
New stone extending apron	C. Yd.	133	
Jelli packing repairs to apron	Do	100	

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Holalu Tank, Registered No. 866, Hassan Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

E. B. SUBRAYAN,
Executive Engineer.

KADUR DIVISION.

ADVERTISEMENT.

The 30th January 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 25th February 1888, for restoring the Girzi Tank, Registered No. 1142, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Details of Work.

Description of Work.	Per.	Quantity.	Rate.
Bund—			
Excavation & earthwork, including watering & tamping ..	C. Yd.	17,556	
Rough stone work (Lew)	Do	1,762	
Do old with new jelli	Do	3,420	
Turfing (only front slope)	Sq. Yd.	5,130	
Grade stones as per standard design	No.	83	
Bench Mark stones..	Do	2	
Waste Weir, 100 *feet long*—			
Burnt brick in surki mortar	C. Ft.	1,347	
Burnt stone slabs including fixing in mortar.. ..	S. Ft.	147	
Plastering in surki mortar	Sqr.	6·00	
Rough stonework, new	S. Yd.	167	

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Girzi Tank, Registered No. 1142, Kadur Taluk ;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6 Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. SITARAMA RAO,
Executive Engineer.

Abstract of Meteorological Registers received from Head-Quarters of Districts for the fortnight ending 31st January 1888.

Head-Quarters.	Thermometer. Averages for the half month. 9-30 A. M. Dry bulb.	Wet bulb.	Difference.	3-30 P. M. Dry bulb.	Wet bulb.	Difference.	Thermometer. Maximum.	Minimum.	Rain. Inches.	Cents.	Wind.
Kolar ...	74	...	...	76	...	...	..	...	...	...	N. E.
Hassan ...	57	54	3	67	63	4	78	59	...	...	E. & N.E.
Shimoga ...	70	...	...	77	...	...	...	...	...	...	S. W.
Kadur ...	66	58	8	75	63	12	76	53	...	...	N. E.
Chitaldroog ..	77	...	...	82	...	...	...	...	...	...	E. & S. E.
Mysore* ...	...	...	...	...	...	...	...	...	...	...	...
Tumkur* ...	...	...	...	...	...	...	...	...	...	...	...

*Information not received.